



Engineering Specifications

**FM-200™ Clean Agent
Fire Suppression System
with AUTOPULSE Z-20 Agent
Releasing Control Panel**

**ANSUL® FM-200* CLEAN AGENT FIRE SUPPRESSION SYSTEM
WITH AUTOPULSE Z-20 RELEASING CONTROL SYSTEM**

ENGINEERING SPECIFICATIONS

2016 - NOVEMBER

Tyco Fire Protection Products
One Stanton Street
Marinette, WI 54143-2542
1-800-862-6785 / 1-715-735-7411

PART 1 – GENERAL

1.1 DESCRIPTION OF WORK:

- A. This specification outlines the requirements for a “Total Flood” Clean Agent Fire Suppression System with automatic detection and control. The work described in this specification includes all engineering, labor, materials, equipment and services necessary, and items required to complete and test the fire suppression system.

1.2 APPLICABLE STANDARDS AND PUBLICATIONS:

- A. The design, equipment, installation, testing, and maintenance of the Clean Agent Fire Suppression System shall be in accordance with the applicable requirements set forth in the latest edition of the following codes and standards:
1. National Fire Protection Agency (NFPA) No. 2001 – Clean Agent Fire Extinguishing Systems
 2. NFPA No. 70 – National Electrical Code
 3. NFPA No. 72 – National Fire Alarm Code
 4. Factory Mutual Approval Guide
 5. UL Listings
 6. Requirements of the Authority Having Jurisdiction (AHJ)
- B. The standards listed, as well as all other applicable codes, standards, and good engineering practices, shall be used as “minimum” design standards.

1.3 REQUIREMENTS:

- A. The suppression system installation shall be made in accordance with the drawings, specifications, and applicable standards. Should a conflict occur between the drawings and specifications, the specifications shall prevail.

1.4 EXCLUSIONS:

- A. The work listed below shall be provided by others or under other sections of this specification:
1. 120 VAC or 220 VAC power supply to the system control panel.
 2. Interlock wiring and conduit for shutdown of HVAC, dampers, and/or electric power supplies, relays, or shunt trip breakers.
 3. Connection to local/remote fire alarm systems, listed central alarm station(s), or sprinkler pre-action/deluge valve actuation.

1.5 GENERAL

A. MANUFACTURER:

1. The manufacturer of the suppression system hardware and detection components shall be Tyco Fire Protection Products (hereinafter referred to as "Tyco").
2. The name of the manufacturer shall appear on all major components.
3. All devices, components, and equipment shall be the products of the same manufacturer.
4. All devices, components, and equipment shall be new, standard products of the manufacturer's latest design and suitable to perform the functions intended.
5. All devices and equipment shall be UL Listed and FM Approved.
6. Locks for all cabinets shall be keyed alike.

B. INSTALLER:

1. The installing contractor shall be trained by Tyco to design, install, test, and maintain fire suppression systems.
2. When possible, the installing contractor shall employ a NICET certified special hazard designer, Level II or above, who will be responsible for this project.
3. The installing contractor shall be an experienced firm regularly engaged in the installation of automatic Clean Agent, or similar fire suppression systems in strict accordance with all applicable codes and standards.
4. The installing contractor must have a minimum of 5 years experience in the design, installation, and testing of Clean Agent, or similar fire suppression systems. A list of systems of a similar nature and scope shall be provided on request.
5. The installing contractor shall show evidence that his company carries a minimum \$2 million liability and complete operations insurance policy. These limits shall supersede limits required in the general conditions of the specifications.
6. The installing contractor shall maintain, or have access to, a clean agent recharging station. The installing contractor shall provide proof of his ability to recharge the largest Clean Agent system within 24 hours after a discharge. Include the amount of bulk agent storage available.
7. The installing contractor shall be an authorized stocking distributor of the Clean Agent system equipment so that immediate replacement parts are available from inventory.
8. The installing contractor shall show proof of emergency service available 24 hours a day, 7 days a week.

C. SUBMITTALS:

1. The installing contractor shall submit the following design information and drawings for approval prior to starting work on this project:
 - a. Field installation layout drawings having a scale of not less than 1/8 in. (3 mm) = 1 ft 0 in. (0.3 m) or 1:100 detailing the location of all agent storage containers, nozzles, pipe runs including pipe sizes and lengths, control panel(s), detectors, manual pull stations, abort stations, audible and visual alarms, etc.
 - b. Auxiliary details and information such as maintenance panels, door holders, special sealing requirements, and equipment shutdown.
 - c. Separate layouts or drawings shall be provided for each level, (i.e. room, under floor, and above ceiling) and for mechanical and electrical work.
 - d. A separate layout or drawing shall show isometric details of agent storage containers, mounting details, proposed pipe runs and sizes, and symbol legend.
 - e. Electrical layout drawings shall show the location of all devices, and include point-to-point conduit runs, and a description of the method(s) used for detector mounting.
 - f. Provide an internal control panel wiring diagram, which shall include power supply requirements and field wiring termination points.
 - g. Separate drawing providing symbol legend to identify all symbols used.
 - h. Annunciator wiring schematics and dimensioned display panel illustration shall be provided. (Optional device)
 - i. Complete hydraulic flow calculations, from a UL Listed computer program, shall be provided for all engineered Clean Agent systems. Calculation sheet(s) must include the manufacturer's name and UL listing number for verification. The individual sections of pipe and each fitting to be used, as shown on the isometrics, must be identified and included in the calculation. Total agent discharge time must be shown and detailed by zone.
 - j. Provide calculations for the battery stand-by power supply taking into consideration the power requirements of all alarms, initiating devices, and auxiliary components under full load conditions.
 - k. A complete sequence of operation shall be submitted detailing all alarm devices, shutdown functions, remote signaling, damper operation, time delay, and agent discharge for each zone or system.
2. Submit drawings, calculations, and system component data sheets for approval to the local fire prevention agency, owner's insurance underwriter, and all other authorities having jurisdiction before starting installation. Submit approved plans to the Architect Engineer for record.

PART 2 – SYSTEM REQUIREMENTS

2.1 SYSTEM DESCRIPTION AND OPERATION:

- A. The system shall be a Total Flood FM-200 Fire Suppression System supplied by Tyco.
- B. The system shall provide the FM-200 fire extinguishant minimum design concentration of 6.7% (UL) or 7.17% (FM) by volume for Class A hazards and a minimum of 8.97% by volume for Class B hazards, in all areas and/or protected spaces, at the minimum anticipated temperature within the protected area. For Class C hazards, a minimum design concentration of 7.2% (UL) or 8.1% (FM) by volume shall be provided. System design shall not exceed 10.5% for normally occupied spaces, adjusted for maximum space temperature anticipated, with provisions for room evacuation before agent release.
- C. The system shall be complete in all ways. It shall include all mechanical and electrical installation, all detection and control equipment, agent storage containers, FM-200 agent, discharge nozzles, pipe and fittings, manual release and abort stations, audible and visual alarm devices, auxiliary devices and controls, shutdowns, alarm interface, caution/advisory signs, functional checkout and testing, training and all other operations necessary for a functional, UL Listed and FM Approved FM-200 Clean Agent Fire Suppression System.
- D. Provide 2 inspections during the first year of service. Inspections shall be made at 6 month intervals commencing when the system is first placed into normal service.
- E. The general contractor shall be responsible for sealing and securing the protected spaces against agent loss and/or leakage during the “hold” period, which is a minimum period of 10 minutes or a time period sufficient to allow for response by trained personnel.
- F. The FM-200 system shall be automatically actuated by either counting zone detection or cross-zoned detection methodology. Smoke sensors / detectors shall utilize photoelectric technology and/or Aspiration Smoke Detectors (ASD) for very early warning smoke detection. Smoke detectors and ASD sample points shall be installed at no more than 250 ft² (23.2 m²) of coverage per detector. When using analog addressable sensors or ASD detectors offering pre-alarm thresholds, further system design consideration is suggested for providing very early warning detection which can offer extended investigation time prior to suppression agent release. In all cases, the compatibility listings of the detectors for use with the control unit should be observed. The system shall require two detectors in alarm prior to automatic agent release.

Both Photoelectric and ASD type smoke detectors can be combined in the releasing process, using one of following methods:

- 1. 1st alarm ASD / 2nd alarm ASD
- 2. 1st alarm ASD / 2nd alarm Photoelectric Detector
- 3. 1st alarm Photoelectric Detector / 2nd alarm Photoelectric Detector

G. SEQUENCE OF OPERATION

- 1. Activation of any single detector in any detection zone shall:
 - a. Cause a first-stage alarm.
 - b. Energize a lamp on the activated detector and identify detector on the display of the control panel (and remote annunciator, if included).

Note: The shutdown of electrical equipment will be optional based on requirements of the local AHJ or applicable standards.

2. Activation of a second smoke detector shall:
 - a. Transmit an alarm signal to remote monitoring or building alarm panel.
 - b. Cause a second-stage (pre-discharge) Audio/Visual alarm to operate.
 - c. Operate auxiliary contacts for air conditioning shutdowns and automatic dampers.
 - d. Initiate a programmable pre-discharge time delay (FM-200 agent release).
3. Upon completion of the time delay the FM-200 system shall:
 - a. Cause a discharge alarm to be activated.
 - b. Operate auxiliary contacts for emergency power off of all electrical equipment (excluding lighting and emergency circuits for life safety).
 - c. Activate visual alarms (strobe) at protected area entrance.
 - d. Energize control solenoid for FM-200 container, releasing gaseous agent into the protected area.

H. AUXILIARY COMPONENTS

1. Double action manual releasing stations shall be provided at each exit of the protected area, and shall, when activated, release the FM-200 agent and cause all audible / visual alarms to activate. In addition, activation of the manual releasing stations shall cause immediate shutdown of air and power circuits.
2. Abort station shall be provided at each exit of the protected area, and shall, when operated, interrupt the pre-discharge time delay of the FM-200 agent and emergency power-off functions. The abort station shall be momentary devices (dead-man) requiring constant pressure to maintain contact closure.

Note: Manual Releasing Station activation shall override any abort station. Abort station operation shall be per IRI and FM guidelines.

2.2 MATERIALS AND EQUIPMENT:

A. GENERAL REQUIREMENTS:

1. The FM-200 Clean Agent System materials and equipment shall be standard products of the supplier's latest design and suitable to perform the functions intended. When one or more pieces of equipment must perform the same function(s), they shall be duplicates produced by one manufacturer.
2. All devices and equipment shall be UL Listed and FM Approved.

B. FM-200 AGENT STORAGE AND DISTRIBUTION:

1. Each system shall have its own supply of clean agent.
2. The system design can be modular, central storage, or a combination of both design criteria.
3. Systems shall be designed in accordance with the manufacturer's guidelines.
4. Each supply shall be located within the hazard area, or as near as possible, to reduce the amount of pipe and fittings required to install the system.
5. The clean agent shall be stored in ANSUL® agent storage containers. Containers shall be super-pressurized with dry nitrogen to an operating pressure of 360 psi at 70 °F (24.8 bar at 21 °C). Containers shall be of high-strength low alloy steel construction and conform to NFPA 2001.
6. Containers shall be actuated by a resettable electric actuator with mechanical override located at each agent container or connected bank of cylinders. Non-resettable or explosive devices shall not be permitted.

7. Each container shall have a pressure gauge and low pressure switch to provide visual and electrical supervision of the container pressure. The low-pressure switch shall be wired to the control panel to provide an audible and visual "Trouble" alarms in the event the container pressure drops below 290 psi to 294 psi (19.9 psi to 20.3 bar). The pressure gauge shall be color coded to provide an easy, visual indication of container pressure.
8. Each container shall have a pressure relief provision that automatically operates before the internal pressure exceeds 774.5 psi (53.4 bar) \pm 5%.
9. Engineered discharge nozzles shall be provided within the manufacturer's guidelines to distribute the FM-200 agent throughout the protected spaces. The nozzles shall be designed to provide proper agent quantity and distribution:
 - a. Nozzles shall be available in 3/8 in. through 2 in. pipe sizes. Each size shall be available in 180° and 360° distribution patterns.
 - b. Ceiling plates can be used with the nozzles to conceal pipe entry holes through ceiling tiles.
10. Distribution piping and fittings shall be installed in accordance with the manufacturer's requirements, NFPA 2001 and approved piping standards and guidelines. All distribution piping shall be installed by qualified individuals using accepted practices and quality procedures. All piping shall be adequately supported and anchored at all directional changes and nozzle locations:
 - a. Before assembly, all piping shall be reamed, blown clear, and swabbed with suitable solvents to remove burrs, mill varnish, and cutting oils.
 - b. All pipe threads shall be sealed with Teflon tape pipe sealant applied to the male thread only.

C. CONTROL SYSTEMS – GENERAL

1. All control systems shall be UL Listed and FM Approved, and shall be utilized with listed or approved compatible operating devices, and shall be capable of the following features:
 - a. Ground fault indication
 - b. Supervised detection circuit(s)
 - c. Supervised alarm circuit(s)
 - d. Supervised release circuit(s)
 - e. Supervised manual release circuit (if applicable)
 - f. Supervised primary power circuit
 - g. Battery standby
 - h. 4.3" color touchscreen LCD operator interface and LED indicating lamps
 - i. Key lock steel enclosure
 - j. Programmable time delay
 - k. Programmable detection logic
 - l. Microprocessor based logic
 - m. History buffer

D. CONTROL PANEL – AUTOPULSE Z-20 AGENT RELEASING CONTROL PANEL

1. The Fire Alarm Control Panel (FACP) shall be an AUTOPULSE Z-20 control panel with the capability of protecting up to 20 hazards. The panel shall contain a Central Processing Unit (CPU) with integral 8 amp power supply which is rated to provide 8 amp for “Special Application” appliances including suppression release peripherals such as horns, strobes and horn/strobes and rated to 6 amp for “regulated 24 VDC” appliance power. The CPU shall communicate with and control the following types of equipment used to make up the system: addressable and conventional initiating devices, addressable modules, annunciators, and other system controlled devices.
2. System Capacity and General Operation:
 - a. The control panel shall provide up to a 250 addressable point capacity with the capability of expansion to 3 loops.
 - b. The system shall include 4 Class B programmable notification appliance circuits rated at 3 A each.
 - c. The control panel and remote annunciator (optional) shall include a full featured, intuitive color touch screen display capable of supporting up to two languages. The menu-driven interface shall provide color coded system status LEDs, allow for direct control of the fire alarm system and also allow for quick access to more detailed system information.
 - d. The control panel shall provide the following features:
 - 1) Drift Compensation to extend detector accuracy over life.
 - 2) Sensitivity Test meeting requirements of NFPA 72.
 - 3) Maintenance Alert to warn of excessive smoke detector dirt or dust accumulation.
 - 4) System Status Reports to display, export to USB device (or print if optional RS232 module is provided).
 - 5) Rapid manual station reporting (under 2 seconds).
 - 6) Non-Alarm points for general (non-fire) control.
 - 7) Periodic Detector Test conducted automatically by software.
 - 8) Pre-alarm for advanced fire warning.
 - 9) Counting/Cross Zoning with the capability of: counting 2 detectors in alarm, 2 software zones in alarm, or 1 smoke detector and 1 thermal detector in alarm.
 - 10) March time and temporal coding options.
 - 11) Walk Test
 - 12) Check for 2 detectors set to same address.
 - 13) The real time clock may also be used to control non-fire functions at programmed time-of-day, day-of-week, and day-of-year.
 - 14) Day/Night automatic adjustment of detector sensitivity.
 - 15) Device Blink Control for sleeping areas.
 - 16) Discrete status LEDs for Alarm, Priority 2, Supervisory, Trouble, Alarm Silenced and AC power indications plus three additional programmable LEDs with associated control switches with provisions for custom labels.
 - 17) The control panel shall be capable of coding Notification circuits in Slow March Time (20 BPM), Fast March Time (120 BPM) and Temporal Code (NFPA 72).

3. Central Microprocessor:
 - a. The microprocessor unit shall communicate with, monitor, and control all external interfaces with the control panel. It shall include system program storage in non-volatile memory for building-specific program storage, and a "watch dog" timer circuit to detect and report microprocessor failure.
 - b. The microprocessor unit shall contain and execute all control-by-event programs for specific action to be taken if an alarm condition is detected by the system. Such control- by-event programs shall be held in non-volatile programmable memory and shall not be lost even if system primary and secondary power failure occurs.
 - c. The microprocessor unit shall also provide a real-time clock for time annotation of system displays and history file.
4. Display:
 - a. The touch screen display shall provide all the controls and indicators used by the system operator.
 - b. The display shall include status information and custom alphanumeric labels for all addressable and conventional detectors, addressable modules, and software zones.
 - c. The display shall be a 4.3 inch color touch screen display.
5. Signaling Line Circuit (SLC):
 - a. The SLC interface called an IDNet+ circuit, shall provide power to and communicate with up to 250 addressable points which can include Photoelectric or Thermal detectors along with all monitoring and control points. This can be accomplished over one to three SLC loops and shall be capable of NFPA 72 Class A or B wiring.
 - b. The loop interface board(s) shall receive and process information from all detectors to determine whether normal, alarm, supervisory or trouble conditions exist for each detector. The software shall automatically maintain the detector's desired sensitivity level by adjusting for the effects of environmental factors, including the accumulation of dust in each detector. The information shall also be used for automatic detector testing and for the automatic determination of detector maintenance requirements.
 - c. The detector software shall meet NFPA 72, requirements and be certified by UL as a calibrated sensitivity test instrument.
 - d. The detector software shall allow manual or automatic sensitivity adjustment.
6. Enclosures:
 - a. The control panel shall be housed in a UL listed cabinet suitable for surface or semi-flush mounting. Cabinet and front shall be corrosion protected, given a rust-resistant prime coat, and manufacturer's standard finish.
 - b. The door shall provide a key lock and include a glass or other transparent opening for viewing of all indicators.
7. All interfaces and associated equipment are to be protected so they will not be affected by voltage surges or line transients consistent with UL standard 864.
8. Optional modules shall be available for NFPA 72 supervising station and public emergency alarm reporting systems. The control panel shall have the ability to meet the latest requirements of UL 864 for delayed AC fail reporting.

9. Power Supply:
 - a. The power supply shall operate on 120 or 240 VAC, 50/60 Hz, and shall provide all necessary power for the control panel. The power supply shall have a 6 A output rating which provides current for special application devices, IDNet devices, module currents and auxiliary output currents. When NACs are controlling regulated 24 DC appliances, total NAC current available shall be 3 A.
 - b. It shall provide a battery charger for 24 hours of standby using dual-rate charging techniques for fast battery recharge.
 - c. It shall provide an earth detection circuit capable of detecting earth faults on I/O modules field wired circuits connected to power supply.
 - d. It shall be power-limited using Positive Temperature Coefficient (PTC) resistors and solid state circuits.
10. Field Wiring Terminal Blocks:
 - a. For ease of service, all panel I/O wiring terminal blocks shall have sufficient capacity for 18 to 12 AWG wire.
11. Field Programming:
 - a. All programming shall be accomplished through a standard PC laptop.
 - b. All field defined programs shall be stored in non-volatile memory.
 - c. The programming function shall be enabled with a password that may be defined specifically for the system when it is installed. Three levels of password protection shall be provided in addition to a key-lock cabinet. One level is used for status level changes such as zone disable or manual on/off commands. A third level (higher-level) is used for actual change of program information.
 - d. A special program check function shall be provided to detect common operator errors.
 - e. For flexibility, an off-line programming function with batch upload/download shall also be available.
12. Specific System Operations:
 - a. Smoke Detector Sensitivity Adjust: Means shall be provided for adjusting the sensitivity of any or all analog intelligent smoke detectors in the system from the system keypad. Sensitivity range shall be within the allowed UL window.
 - b. Alarm Verification: Verification is implemented using zones with 512 zones available. The alarm verification delay shall be programmable from 5 to 30 seconds and each zone shall be able to be selected for verification. The control panel shall keep a count of the number of times that each zone has entered the verification cycle. These counters may be displayed and reset by the proper operator commands.
 - c. Point Disable: Any device in the system may be Enabled or Disabled through the system keypad.
 - d. Point Read: The system shall be able to display or print the following point status diagnostic functions:
 - 1) Device status.
 - 2) Device type.
 - 3) Custom device label.
 - 4) View analog detector values.
 - 5) Device zone assignments.
 - 6) All program parameters.

- e. System Status Reports: Upon command from a system operator, a status report will be generated and printed listing all system status provided an optional RS232 card is installed. The report must also be exportable to a USB device on the Z-20 USB port
- f. System History Recording and Reporting: The control panel shall contain a history buffer that will be capable of storing up to 2000 events (1000 alarm and 1000 trouble). Each of these activations will be stored and time-and-date stamped with the actual time of the activation. The contents of the history buffer may be manually reviewed, one event at a time, exported to a USB device or printed (if optional RS232 module is provided) in its entirety.
 - 1) The history buffer shall use non-volatile memory. Systems that use volatile memory for history storage are not acceptable.
- g. Automatic Detector Maintenance Alert: The control panel shall automatically interrogate each intelligent smoke detector and analyze the detector responses over a period of time.
 - 1) If any intelligent smoke detector in the system responds with a reading that is below or above normal limits, the system will enter the trouble mode and the particular detector will be annunciated on the system display. This feature shall in no way inhibit the receipt of alarm conditions in the system nor shall it require any special hardware, special tools or computer expertise to perform.
- h. Pre-Alarm Function: The system shall provide 2 levels of pre-alarm warning to give advance notice of a possible fire situation. Both pre-alarm levels shall be fully field adjustable. The first level shall give an audible indication at the panel. The second level shall give an audible indication and may also activate control relays. The system shall also have the ability to activate local detector sounder bases at the pre-alarm level to assist in avoiding nuisance alarms.
- i. Software Zones: The control panel shall provide 512 programmable software zones. All addressable devices may be field programmed to be grouped into these zones for control activation and annunciation purposes.

13. Batteries:

- a. Batteries shall be 12 volt (2 required).
- b. Batteries shall have sufficient capacity to power the fire alarm system for not less than 24 hours in standby plus 5 minutes of alarm upon a normal AC power failure.
- c. Batteries are to be completely maintenance free. No liquids are required. Fluid level checks, refilling, spills and leakage shall not be accepted.

E. PROGRAMMABLE ELECTRONIC SOUNDER

- 1. Electronic sounders shall be UL Listed and FM Approved and operate on 24 VDC nominal.
- 2. Electronic sounders shall be field programmable without the use of special tools to choose 1 of 8 tones with an output sound level of at least 90 dBA measured at 10 ft (3.0 m) from the device.
- 3. Electronic sounders shall be flush or semi-flush mounted as shown on plans.

F. VISUAL NOTIFICATION APPLIANCES

- 1. Strobe lights shall operate on 24 VDC nominal.
- 2. Strobe lights shall meet the requirements of the ADA as defined in UL standard 1971 and shall meet the following criteria:
 - a. The strobe intensity shall meet the requirements of UL 1971 and devices shall be multi-candela 15 cd – 110cd and higher intensity if required by the plans.
 - b. The flash rate shall meet the requirements of UL 1971.

- c. The appliance shall be placed 80 in. (to the bottom of the appliance) to 96 in. (to the top of the appliance) above the finished floor within the space.

G. AUDIBLE/VISUAL COMBINATION DEVICES

1. Audible/visual combination devices shall meet the applicable requirements of Section 3.5 listed above for audibility.
2. Audible/visual combination devices shall meet the requirements of Section 3.6 (listed above) for visibility.

H. ADDRESSABLE DEVICES – GENERAL

1. Addressable devices shall provide an address-setting means using dip switches.
2. Detectors shall be intelligent and addressable, and shall connect with 2 wires to the fire alarm/release control panel signaling line circuits.
3. Addressable smoke and thermal detectors shall provide dual alarm and power LEDs. Both LEDs shall flash under normal conditions indicating that the detector is operational and in regular communication with the control panel. Both LEDs shall be placed into steady illumination by the control panel indicating that an alarm condition has been detected. If required, the flashing mode operation of the detector LEDs shall be optional through the system field program. An output connection shall also be provided in the base to connect an external remote alarm LED.
4. Smoke detector sensitivity shall be set through the control panel and shall be adjustable in the field through the field programming of the system. Sensitivity may be automatically adjusted by the panel on a time-of-day basis.
5. Using software in the control panel, detectors shall automatically compensate for dust accumulation and other slow environmental changes that may affect their performance. The detectors shall be listed by UL as meeting the calibrated sensitivity test requirements of NFPA Standard 72.
6. The detectors shall be ceiling-mount and shall include a separate twist-lock base with tamper-proof feature. An optional base shall be available with a built-in (local) sounder rated at 85 dBA minimum.
7. The detectors shall provide a test means whereby they will simulate an alarm condition and report that condition to the control panel. Such a test may be initiated at the detector itself (by activating a magnetic switch) or initiated remotely on command from the control panel.
8. Detectors shall also store an internal identifying type code that the control panel shall use to identify the type of device (PHOTO or THERMAL).

I. ADDRESSABLE MANUAL PULL STATION

1. Addressable manual pull station shall, on command from the control panel, send data to the panel representing the state of the manual switch. They shall use a key operated test-reset lock and shall be designed so that after actual emergency operation, they cannot be restored to normal use except by the use of a key.
2. All operated stations shall have a positive, visual indication of operation and utilize a key-type reset.
3. Manual stations shall be clearly visible operating instructions provided on the cover. The word AGENT shall appear on the front and both sides of the stations.
4. Stations shall be suitable for surface mounting or semi-flush mounting as shown on the plans, and shall be installed not less than 42 in. (1.1 m), nor more than 48 in. (1.2 m) above the finished floor.
5. Operation shall require 2 actions.

J. ANALOG ADDRESSABLE PHOTOELECTRIC SMOKE DETECTOR

1. The detectors shall use the photoelectric (light-scattering) principle to measure smoke density and shall, on command from the control panel, send data to the panel representing the analog level of smoke density.

K. ANALOG ADDRESSABLE HEAT DETECTOR

1. Heat detectors shall be analog addressable devices rated at 135 °F (57 °C) and have a rate-of-rise element rated at 15 °F (9.4 °C) per minute. It shall connect via 2 wires to the control panel signaling line circuit. Up to 159 intelligent heat detectors may connect to one SLC loop.
2. The detectors shall use an electronic sensor to measure thermal conditions caused by a fire and shall, on command from the control panel, send data to the panel representing the analog level of such thermal measurements.
3. An optional, intelligent heat detector shall be available for applications which do not require a rate- of-rise element.

L. ANALOG ADDRESSABLE DUCT SMOKE DETECTOR

1. In-duct smoke detector housing shall accommodate an intelligent photoelectric sensor which provides continuous analog monitoring and alarm verification from the panel.
2. When sufficient smoke is sensed, an alarm signal is initiated at the control panel and appropriate action is taken to change over air handling systems to help prevent the rapid distribution of toxic smoke and fire gases throughout the areas served by the duct system.

M. ADDRESSABLE DRY CONTACT MONITOR MODULE

1. Addressable monitor modules shall be provided to connect one supervised IDC zone of conventional alarm initiating devices (any N.O. dry contact device) to one of the control panel SLC loops.
2. The monitor module shall mount in a 4 in. (102 mm) square, 2 1/8 in. (54 mm) deep electrical box.
3. The IDC zone may be wired for Style D or Style B operation. An LED shall be provided that shall flash under normal conditions indicating that the monitor module is operational and in regular communication with the control panel.
4. For difficult to reach areas, the monitor module shall be available in a miniature package and shall be no larger than 2-3/4 in. x 1-1/4 in. x 1/2 in. (69.9 mm x 31.8 mm x 12.7 mm). This version need not include Style D or an LED.

N. ADDRESSABLE TWO-WIRE DETECTOR MONITOR MODULE

1. Addressable monitor modules shall be provided to connect one supervised IDC zone of conventional two-wire smoke detectors or alarm initiating devices (any N.O. dry contact device).
2. The two-wire monitor module shall mount in a 4 in. (102 mm) square, 2 1/8 in. (54 mm) deep electrical box or with an optional surface back box.
3. The IDC zone may be wired for Class A or B (Style D or Style B) operation. An LED shall be provided that shall flash under normal conditions indicating that the monitor module is operational and in regular communication with the control panel.
4. Smoke Detectors:
 - a. Smoke detectors shall be 24 VDC and shall be UL Listed and FM approved.
 - b. Each detector shall include a visual status indicator, provide remote LED output, and include a built-in test capability.
 - c. The sensitivity shall be factory set per UL 268.
 - d. The detector cover and screen shall be easily removable for field cleaning.
 - e. A special vandal-resistant locking screw shall be provided to lock the head to the base.

- f. The head-to-base connection shall be made by use of bifurcated contacts. Terminal connections to the base shall be of the screw type that are accessible with the base installed on the mounting box.
- g. Where specifically identified on the contract drawings, detector bases shall incorporate a relay with Form C contacts rated at 1 amp at 120 VAC and 2 amps at 28 VDC.
- h. Photoelectric-type smoke detector shall be light reflective type and compatible with the AUTOPULSE control system. The detector shall have an LED in its base which is illuminated in a steady-on mode when in alarm and pulse mode when in standby. Reset of the detector shall be performed by the control unit reset switch.
- i. The design of the photoelectric detector compensating circuits shall provide stable operation with regard to minor changes in temperature, humidity and atmospheric conditions.
- j. Photoelectric-type smoke detector with heat detector shall be light reflective type and compatible with the AUTOPULSE control system. The detector shall have an LED in its base which is illuminated in a steady-on mode when in alarm and pulse mode when in standby. Reset of the detector shall be performed by the control unit reset switch.

O. ADDRESSABLE CONTROL MODULE

- 1. Addressable control modules shall be provided to supervise and control the operation of one conventional Notification Appliance Circuit (NAC) of compatible, 24 VDC powered, polarized audio/visual notification appliances. For fan shutdown and other auxiliary control functions, the control module may be set to operate as a dry contact relay.
- 2. The control module shall mount in a standard 4 in. (102 mm) square, 2 1/8 in. (54 mm) deep electrical box, or to a surface mounted back box.
- 3. The control module NAC circuit may be wired for Style Z or Style Y (Class A/B) with up to 1 amp of inductive A/V signal, or 2 amps of resistive A/V signal operation, or as a dry contact (Form C) relay. The relay coil shall be magnetically latched to reduce wiring connection requirements and to insure that 100% of all auxiliary relay or NACs may be energized at the same time on the same pair of wires.
- 4. Audio/visual power shall be provided by a separate supervised power loop from the main control panel or from a supervised, UL listed remote power supply.
- 5. The control module shall provide address-setting means using decimal switches and shall also store an internal identifying code that the control panel shall use to identify the type of device. An LED shall be provided that shall flash under normal conditions indicating that the control module is operational and is in regular communication with the control panel.
- 6. A magnetic test switch shall be provided to test the module without opening or shorting its NAC wiring.
- 7. The control module shall be suitable for pilot duty applications and rated for a minimum of 0.6 amps at 30 VDC.

P. ISOLATOR MODULE

- 1. Isolator modules shall be provided to automatically isolate wire-to-wire short circuits on an SLC loop. The isolator module shall limit the number of modules or detectors that may be rendered inoperative by a short circuit fault on the SLC Loop. At least one isolator module shall be provided for each floor or protected zone of the building.
- 2. If a wire-to-wire short occurs, the isolator module shall automatically open-circuit (disconnect) the SLC loop. When the short circuit condition is corrected, the isolator module shall automatically reconnect the isolated section.
- 3. The isolator module shall not require any address-setting and its operations shall be totally automatic. It shall not be necessary to replace or reset an isolator module after its normal operation.

4. The isolator module shall mount in a standard 4 in. (102 mm) deep electrical box or in a surface mounted back box. It shall provide a single LED that shall flash to indicate that the isolator is operational and shall illuminate steadily to indicate that a short circuit condition has been detected and isolated.

Q. ABORT SWITCH

1. The abort switch shall be used where an investigative delay is desired between detection and actuation of the fire suppression system.
2. This switch shall be a momentary contact "dead-man" type switch requiring constant pressure to transfer one set of contacts. Clear operating instructions shall be provided at the abort switch.
3. This switch shall be rated for 2 A resistive @ 30 VDC.
4. The terminal connections shall be of the screw type.

R. MAINTENANCE LOCK-OUT SWITCH

1. The maintenance lock-out switch shall be used where it is desired to disable the fire suppression system during routine maintenance.
2. This switch shall be key operated allowing removal of the key only in "Normal" position. A red indicator lamp shall be included on the switch assembly to be illuminated when in the "Lock-Out" position. The control unit is used to indicate a supervisory condition when in the "Lock-Out" position.
3. The switch shall include 1 set of normally open and 1 set of normally closed control contacts rated for 2 A resistive @ 30 VDC.
4. The terminal connections shall be of the screw type.

S. SELECTOR SWITCH

1. The selector switch shall be used where a connected reserve is required.
2. This switch shall be key operated allowing removal of the key in either the "Main" or "Reserve" position.
3. This switch shall be rated at 28 VDC @ 1.1 amp make/break or 6 amp continuous carry.
4. The terminal connections shall be of the screw type.

T. WATER FLOW SWITCHES

1. Flow switches shall be integral, mechanical, non-coded, non-accumulative retard type.
2. Flow switches shall have an alarm transmission time delay that is conveniently adjustable from 0 to 60 seconds. Initial settings shall be 30 or 45 seconds.
3. Flow switches shall be located a minimum of 1 ft (0.3 m) from a fitting that changes the direction of the flow and a minimum of 3 ft (0.9 m) from a valve.

U. SPRINKLER AND STANDPIPE VALVE SUPERVISORY SWITCHES

1. Each sprinkler system water supply control valve riser, or zone control valve, and each standpipe system riser control valve shall be equipped with a supervisory switch. Standpipe hose valves, and test and drain valves shall not be equipped with supervisory switches.
2. Each Post Indicator Valve (PIV) or main gate valve shall be equipped with a supervisory switch.
3. The switch shall be mounted so as not to interfere with the normal operation of the valve and adjusted to operate within 2 revolutions toward the closed position of the valve control, or when the stem has moved no more than one-fifth of the distance from its normal position.

4. The mechanism shall be contained in a weatherproof aluminum housing that shall provide a 3/4 in. tapped conduit entrance and incorporate the necessary facilities for attachment to the valves.
5. Switch housing to be finished in red baked enamel.
6. The entire installed assembly shall be tamper proof and arranged to cause switch operation if the housing cover is removed or if the unit is removed from its mounting.
7. Valve supervisory switches shall be provided and connected under this section and installed by mechanical contractor.

V. COLOR TOUCHSCREEN REMOTE LCD ANNUNCIATOR

1. The remote annunciator shall provide a 4.3" color touchscreen LCD display that is identical to the control panel user interface. The annunciator shall be capable of displaying a custom background image when the system status is normal.
2. The annunciator shall provide; a local sounder; discrete status LEDs for Alarm, Priority 2, Supervisory, Trouble, Alarm Silenced and AC power indications; and three programmable LEDs with associated control switches with provisions for custom labels. A lamp test feature shall be available from the display menu.
3. The remote annunciator shall provide access to all system status information, controls, diagnostics, and reports that are available on the control unit user interface. Protected access shall be provided to the following operator control functions and diagnostics; Alarm, Priority 2, Supervisory and Trouble Acknowledge; Alarm Silence; and System Reset; Hardware Reset; Point Disable/Enable; Annunciator Sounder Silence, Clear History Logs; Panel Setup; and System Diagnostics. Protection against unauthorized use shall be provided via a passcode, keyswitch, or both.
4. The annunciator shall have the capability to support up to two languages with the ability to toggle between languages using one of the programmable control switches on the annunciator.
5. The annunciator shall connect to a two-wire Remote Unit Interface (RUI). The two-wire RUI connection shall be capable of distances of up to 2,500 feet (762 meters).
6. The system shall support up to 6 remote color touchscreen LCD annunciators.

W. CAUTION AND ADVISORY SIGNS:

1. Signs shall be provided to comply with NFPA 2001 and the recommendations of the FM-200 agent equipment supplier:
 - a. Entrance sign: 1 required at each entrance to a protected space.
 - b. Manual discharge sign: 1 required at each manual discharge station.
 - c. Flashing light sign: 1 required at each flashing light over each exit from a protected space.

X. SYSTEM AND CONTROL WIRING:

1. All system wiring shall be furnished and installed by the contractor.
2. All wiring shall be installed in electrical metallic tubing (EMT or conduit) and must be installed and kept separate from all other building wiring.
3. All system components shall be securely supported independent of the wiring. Runs of conduit and wiring shall be straight, neatly arranged, properly supported, and installed parallel and perpendicular to walls and partitions.
4. The sizes of the conductors shall be those specified by the manufacturer. Color-coded wire shall be used. All wires shall be tagged at all junction points, and shall be free from shorts, earth connections (unless so noted on the system drawings), and crosses between conductors. Final terminations between the control panel and the system field wiring shall be made under the direct supervision of a factory-trained representative.

5. All wiring shall be installed by qualified individuals in a neat and workmanlike manner to conform to the National Electrical Code, Article 725 and Article 760, except as otherwise permitted for limited energy circuits, as described in NFPA 72. Wiring installation shall meet all local, state, province, and/or country codes.
6. The complete system electrical installation and all auxiliary components shall be connected to earth ground in accordance with the National Electrical Code.

PART 3 – TESTING AND DOCUMENTATION**3.1 SYSTEM INSPECTION AND CHECKOUT:**

- A. After the system installation has been completed, the entire system shall be checked out, inspected, and functionally tested by qualified, trained personnel, in accordance with the manufacturer's recommended procedures and NFPA standards:
1. All containers and distribution piping shall be checked for proper mounting and installation.
 2. All electrical wiring shall be tested for proper connection, continuity, and resistance to earth.
 3. The complete system shall be functionally tested in the presence of the owner or his representative, and all functions, including system and equipment interlocks, must be operational at least 5 days prior to the final acceptance tests:
 - a. Each detector shall be tested in accordance with the manufacturer's recommended procedures, and test values recorded.
 - b. All system and equipment interlocks, such as door release devices, audible and visual devices, equipment shutdowns, local and remote alarms, etc. shall function as required and designed.
 - c. Each control panel circuit shall be tested for trouble by inducing a trouble condition into the system.

3.2 TRAINING REQUIREMENTS:

- A. Prior to final acceptance, the installing contractor shall provide operational training to each shift of the owners personnel. Each training session shall include control panel operation, manual and (optional) abort functions, trouble procedures, supervisory procedures, auxiliary functions, and emergency procedures.

3.3 OPERATION AND MAINTENANCE:

- A. Prior to final acceptance, the installing contractor shall provide complete operation and maintenance instruction manuals. Four copies of the instruction manuals shall be provided for each system to the owner. All aspects of system operation and maintenance shall be detailed, including piping isometrics, wiring diagrams of all circuits, a written description of the system design, sequence of operation and drawing(s) illustrating control logic, and equipment used in the system. Checklists and procedures for emergency situations, troubleshooting techniques, maintenance operations and procedures shall be included in the manual.

3.4 AS-BUILT DRAWINGS:

- A. Upon completion of each system, the installing contractor shall provide 4 copies of system "As-Built" drawings to the owner. The drawings shall show actual installation details, including all equipment locations (i.e.: control panel(s), agent container(s), detectors, alarms, manuals, and aborts, etc.) as well as piping and conduit routing details. The drawings shall show all room or facilities modifications, including door and/or damper installations completed. One copy of reproducible engineering drawings shall be provided reflecting all actual installation details.

3.5 ACCEPTANCE TESTS:

- A. At the time "As-Built" drawings and maintenance/operations manuals are submitted, the installing contractor shall submit a "Test Plan" describing procedures to be used to test the control system(s). The Test Plan shall include a step-by-step description of all tests to be performed, and shall indicate the type and location of test apparatus to be employed. The tests shall demonstrate that the operational and installation requirements of this specification have been met. All tests shall be conducted in the presence of the owner and shall not be conducted until the Test Plan has been approved.

- B. The tests shall demonstrate that the entire control system functions as designed and intended. All circuits shall be tested: automatic actuation, solenoid and manual actuation, HVAC and power shutdowns, audible and visual alarm devices, and manual override of abort functions. Supervision of all panel circuits, including AC power and battery power supplies, shall be tested and qualified.
- C. A room pressurization test shall be conducted, in each protected space, to determine the presence of openings which would affect the agent concentration levels. The test(s) shall be conducted using the Retro-tec Corp. Door Fan system, or equivalent, with integrated computer program. All testing shall be in accordance with NFPA 2001, Appendix C.
- D. If room pressurization testing indicates that openings exist, which would result in leakage and/or loss of the extinguishing agent, the installing contractor shall be responsible for coordinating the proper sealing of the protected space(s) by the general contractor, or his sub-contractor, or agent. The general contractor shall be responsible for adequately sealing all protected space(s) against agent loss or leakage. The installing contractor shall inspect all work to ascertain that the protected space(s) have been adequately and properly sealed. THE SUPPRESSION SYSTEM INSTALLING CONTRACTOR SHALL BE RESPONSIBLE FOR THE SUCCESS OF THE ROOM PRESSURIZATION TESTS. If the first room pressurization test is not successful, in accordance with these specifications, the installing contractor shall direct the general contractor to determine and correct, the cause of the test failure. The installing contractor shall conduct additional room pressurization tests, at no additional cost to the owner, until a successful test is obtained. Copies of successful test results shall be submitted to the owner for record. Upon acceptance by the owner, the completed system(s) shall be placed into service.

3.6 SYSTEM INSPECTIONS:

- A. The installing contractor shall provide 2 inspections of each system, installed under this contract, during the one-year warranty period. The first inspection shall be at the 6 month interval, and the second inspection at the 12 month interval after system acceptance. Inspections shall be conducted in accordance with the manufacturer's guidelines and the recommendations of NFPA 2001.
- B. Documents certifying satisfactory system(s) operation shall be submitted to the owner upon completion of each inspection.

Note: The Metric and English conversions are rounded as appropriate to stay within maximum and minimum approved values.

ANSUL, AUTOPULSE, and the product names listed in this material are marks and/or registered marks. Unauthorized use is strictly prohibited.

* FM-200 is a trademark of Chemours Chemical Corporation.

END OF SECTION

F-2015172